

Project Information:

Client	Low Carbon Solar
Main Contractor	Isolux Corsan
Blackwell Role	Sub Contractor
Form of Contract	NEC3 Short Form
Contract Start	May 2011
Contract Period	10 weeks
Contract Value	£240,000

Blackwell Site Management:

Project Manager:

Hywel Jones

Site Manager:

Dave Gibson

Commercial Manager:

Allan McCann

Project Office:

Welsh Regional Office:

Phoenix Way, Swansea Enterprise
Park, Swansea SA7 9FZ

Tel. 01792 701348

Fax: 01792 701240



Services Include:

Civil Engineering

Earthworks

Geotechnical

Remediation



Background:

Blackwell was awarded the contract for the construction of one of the first 5MW Solar Farms in the UK, which have a renewable energy source to supply approximately 1,000 homes.

Key Processes:

This was a design and build contract and comprised of the following:

- PV Solar Arrays complete with access roads
- 4No inverter units
- 6.5km of ducting with associated chambers
- CCTV perimeter camera trenches and concrete pad foundations.
- Foundations and base platforms for the inverters and control room.
- Crane Platforms.

